

JSCE Guidelines for Concrete No.8

**RECOMMENDATIONS FOR SHOTCRETING  
(Draft)**

**Contents**

**Part 1 “Tunnels by the NATM”**

**Chapter 1 General..... 1**

1.1 Scope ..... 1

1.2 General ..... 3

1.3 Definitions..... 9

**Chapter 2 Performance establishment..... 10**

2.1 General ..... 10

2.2 Performance establishment for NATM tunnels ..... 12

2.3 Performance establishment for shotcrete..... 12

2.3.1 General ..... 12

2.3.2 Mechanical performance ..... 14

2.3.2.1 Design strength..... 14

2.3.2.2 Initial strength..... 15

2.3.2.3 Bending toughness ..... 17

**Chapter 3 Performance verification..... 19**

3.1 General ..... 19

3.2 Verification for tunnels by the NATM..... 19

3.3 Verification for shotcrete ..... 20

3.3.1 General ..... 20

3.3.2 Verification for mechanical performance ..... 22

3.3.2.1 Verification for design strength ..... 22

3.3.2.2 Verification for initial strength ..... 23

3.3.2.3 Verification for bending toughness..... 24

**Chapter 4 Construction planning ..... 25**

4.1 General ..... 25

4.2 Construction planning for an entire tunnel construction project ..... 26

4.3 Construction planning for shotcreting ..... 27

4.3.1 General ..... 27

4.3.2 Shotcreting process..... 29

4.3.3 Shotcreting procedure..... 32

4.3.4 Gunning operation..... 33

4.3.5	Nozzleman.....	33
4.4	Confirmation of construction planning for shotcreting .....	34
4.4.1	General .....	34
4.4.2	Confirmation of placing performance .....	36
4.4.2.1	Confirmation of pumpability.....	36
4.4.2.2	Confirmation of the rebound ratio.....	38
4.4.2.3	Confirmation of dust concentration.....	41
4.5	Modification of construction planning .....	44

## **Chapter 5 Materials and mix proportion design..... 45**

5.1	General .....	45
5.2	Shotcrete materials .....	45
5.2.1	General .....	45
5.2.2	Cement .....	46
5.2.3	Water .....	46
5.2.4	Aggregates.....	46
5.2.5	Set accelerating agent.....	47
5.2.6	Chemical admixtures.....	48
5.2.7	Mineral admixtures.....	49
5.2.8	Reinforcement .....	50
5.3	Mix proportion design .....	51
5.3.1	General .....	51
5.3.2	Maximum aggregate size.....	52
5.3.3	Unit water content and slump.....	52
5.3.4	Water-cement ratio and unit cement content .....	53
5.3.5	Sand-coarse aggregate ratio.....	53
5.3.6	Dosage of accelerator .....	54
5.3.7	Dosage of admixtures and unit content .....	54
5.3.8	Fiber content.....	54

## **Chapter 6 Production and construction equipment ..... 56**

6.1	General .....	56
6.2	Production equipment.....	56
6.2.1	Storage equipment.....	56
6.2.2	Measurement equipment and auxiliary equipment.....	57
6.2.3	Mixing equipment .....	59
6.3	Production .....	60
6.3.1	Measuring.....	60
6.3.2	Mixing.....	61
6.4	Shotcreting equipment.....	64
6.4.1	General .....	64
6.4.2	Shotcreting machine .....	65
6.4.3	Remote shotcreting equipment.....	66
6.4.4	Accelerator dispensers.....	67
6.4.5	Miscellaneous equipment.....	67
6.4.6	Newly developed shotcreting equipment .....	68

<b>Chapter 7 Construction .....</b>	<b>69</b>
7.1 General .....	69
7.2 Storage of reinforcements.....	69
7.3 Placement of wire fabric.....	70
7.4 Delivery .....	70
7.5 Surface protection.....	71
7.6 Shotcreting .....	72
7.6.1 General .....	72
7.6.2 Velocity and pressure at the nozzle .....	72
7.6.3 Delivery distance.....	73
7.6.4 Angle and distance of gunning.....	74
7.6.5 Buildup of a shotcrete layer.....	75
7.6.6 Placement of steel supports .....	76
7.6.7 Finishing surface of shotcrete.....	77
7.7 Special application .....	77
7.7.1 Shotcreting on water ingress .....	77
7.7.2 Long delivery .....	80
7.7.3 Long transport and length of wait after mixing.....	80
7.7.4 Execution of shotcreting for vertical tunnels or diagonal tunnels .....	81
7.8 Safety and health .....	81
7.8.1 General .....	81
7.8.2 Protection against dust.....	82
7.9 Curing.....	83
7.10 Construction control.....	83
7.10.1 General .....	83
7.10.2 Control of placing performance.....	84
 <b>Chapter 8 Inspection .....</b>	 <b>85</b>
8.1 General .....	85
8.2 Inspection planning .....	87
8.3 Acceptance inspection of materials .....	88
8.3.1 Concrete materials.....	88
8.3.2 Reinforcements.....	89
8.4 Inspection of production equipment.....	89
8.5 Inspection of base concrete .....	90
8.6 Inspection of shotcrete.....	90
8.7 Inspection of application thickness .....	92
8.8 Inspection records.....	92
 <b>Chapter 9 Construction records .....</b>	 <b>93</b>

## Part 2 “Slope Stabilization”

<b>Chapter 1</b>	<b>General</b> .....	<b>95</b>
1.1	Scope .....	95
1.2	Types of shotcreted slope structures.....	100
1.3	Shotcrete for slope stabilization .....	101
1.4	Definitions .....	103
<b>Chapter 2</b>	<b>Performance establishment</b> .....	<b>104</b>
2.1	General .....	104
2.2	Performance establishment for shotcreted slope structures.....	104
2.2.1	General .....	104
2.2.2	Safety.....	106
2.2.3	Performance for hazards to third parties .....	107
2.2.4	Performance for aesthetic appearance and landscape.....	107
2.2.5	Durability .....	108
2.3	Performance establishment for shotcrete for slope stabilization .....	108
2.3.1	General .....	108
2.3.2	Mechanical performance .....	109
2.3.3	Durability .....	110
<b>Chapter 3</b>	<b>Performance verification</b> .....	<b>111</b>
3.1	General .....	111
3.2	Verification for shotcrete structures.....	111
3.2.1	General .....	111
3.2.2	Verification for safety .....	112
3.2.3	Verification for hazards to third parties .....	112
3.2.4	Verification for aesthetic appearance and landscape .....	113
3.2.5	Verification for durability .....	113
3.3	Performance verification of shotcrete members .....	114
3.3.1	Verification for mechanical performance .....	114
3.3.2	Validation of endurance performance.....	115
<b>Chapter 4</b>	<b>Construction planning</b> .....	<b>119</b>
4.1	General .....	119
4.2	Construction planning for a slope shotcrete project .....	119
4.3	Construction planning for a shotcreted slope .....	121
4.4	Determination of shotcrete processes .....	124
4.5	Confirmation of construction planning for slope shotcrete projects .....	125
4.5.1	General .....	125
4.5.2	Confirmation of placing performance .....	126

4.6	Modification of construction planning .....	129
-----	---	-----

**Chapter 5 Materials and mix proportion design..... 130**

5.1	General .....	130
5.2	Shotcrete materials .....	130
5.2.1	General .....	130
5.2.2	Cement .....	131
5.2.3	Water .....	131
5.2.4	Aggregates.....	132
5.2.5	Admixtures .....	133
5.3	Reinforcement .....	134
5.3.1	General .....	134
5.3.2	Selection of reinforcements .....	134
5.3.3	Storage of reinforcements.....	136
5.4	Mix proportion design .....	136
5.4.1	General .....	136
5.4.2	Required average strength .....	136
5.4.3	Mix proportion design .....	138

**Chapter 6 Production and construction equipment ..... 142**

6.1	General .....	142
6.2	Production equipment.....	142
6.2.1	Storage equipment .....	142
6.2.2	Measurement equipment .....	143
6.3	Mixer, gun and accessories.....	144
6.4	Production .....	146
6.4.1	Measuring and preparation of materials .....	146
6.4.2	Mixing .....	146

**Chapter 7 Construction ..... 149**

7.1	General .....	149
7.2	Preparation for shotcreting .....	150
7.3	Assembly of reinforcement, formwork and mesh .....	152
7.4	Shotcreting .....	153
7.5	Safety and health .....	155
7.6	Curing.....	155
7.7	Placement control .....	155
7.7.1	General .....	155
7.7.2	Items and methods for construction management .....	156

**Chapter 8 Inspection..... 158**

8.1	General .....	158
8.2	Inspection planning .....	159

8.3	Acceptance inspection of materials .....	160
8.4	Inspection of production.....	160
8.4.1	General .....	160
8.4.2	Inspection of production equipment.....	161
8.4.3	Inspection of production processes .....	161
8.5	Inspection of reinforcement assembly .....	162
8.6	Inspection of in-place shotcrete.....	163
8.6.1	General .....	163
8.6.2	Inspection of in-place shotcrete.....	164
8.6.3	Quality inspection of in-place shotcrete .....	165
8.7	Inspection of shotcreted slope structure .....	166
8.8	Inspection records.....	166

**Chapter 9 Construction records and maintenance ..... 168**

**Part 3 “Repair and Strengthening”**

**Chapter 1 General..... 171**

1.1	Scope .....	171
1.2	General .....	172
1.3	Definitions.....	175

**Chapter 2 Performance establishment..... 176**

2.1	General .....	176
2.2	Performance establishment for concrete structures .....	177
2.3	Performance level required of a structure .....	178
2.4	Performance establishment for shotcrete.....	180
2.4.1	General .....	180
2.4.2	Mechanical performance .....	182
2.4.3	Cracking resistance.....	183
2.4.4	Durability .....	185
2.4.5	Spalling resistance.....	186
2.4.6	Performance for aesthetic appearance and landscape.....	187

**Chapter 3 Performance verification..... 188**

3.1	General .....	188
3.2	Verification for the structures repaired or strengthened with shotcrete.....	188
3.3	Verification for shotcrete .....	189
3.3.1	General .....	189
3.3.2	Verification for mechanical performance .....	190
3.3.3	Verification for cracking resistance .....	192
3.3.4	Verification for durability .....	194
3.3.5	Verification for spalling resistance .....	196

3.3.6	Verification for aesthetic appearance and landscape .....	196
<b>Chapter 4</b>	<b>Design and construction planning .....</b>	<b>198</b>
4.1	General .....	198
4.2	Selection of construction processes.....	199
4.2.1	Selection of a repair and strengthening process .....	199
4.2.2	Selection of shotcrete processes .....	202
4.3	Repair design.....	203
4.3.1	General .....	203
4.3.2	Procedures for repair design.....	205
4.4	Strengthening design .....	206
4.4.1	General .....	206
4.4.2	Procedures for strengthening design .....	208
4.5	Planning of repair and strengthening projects.....	209
4.5.1	General .....	209
4.5.2	Confirmation of the shotcreting planning.....	210
<b>Chapter 5</b>	<b>Materials and mix proportion design.....</b>	<b>211</b>
5.1	General .....	211
5.2	Shotcrete materials .....	211
5.2.1	General .....	211
5.2.2	Cement .....	213
5.2.3	Water .....	213
5.2.4	Aggregate .....	213
5.2.5	Fibers.....	214
5.2.6	Admixtures.....	215
5.2.7	Premixed materials.....	217
5.3	Basic concept of mix proportion design.....	220
5.3.1	General .....	220
5.3.2	Mix proportion of shotcretes .....	220
5.3.3	Mix proportion of premixed materials .....	221
<b>Chapter 6</b>	<b>Construction .....</b>	<b>223</b>
6.1	General .....	223
6.2	Pre-survey of existing concrete structure .....	224
6.3	Preparatory work .....	225
6.4	Removal of deteriorated concrete.....	226
6.5	Preparation of concrete surface .....	227
6.6	Corrosion protection of reinforcing bars .....	228
6.7	Shotcreting .....	229
6.7.1	General .....	229
6.7.2	Dry-mix process .....	231
6.7.3	Wet-mix process .....	233
6.8	Safety and health .....	235

6.9	Finishing and curing.....	236
6.10	Placement control.....	236
6.10.1	General .....	236
6.10.2	Control of shotcreting.....	237
6.11	Use of another process with the shotcreting method.....	238
<b>Chapter 7 Inspection.....</b>		<b>240</b>
7.1	General .....	240
7.2	Inspection planning .....	241
7.3	Acceptance inspection of materials.....	242
7.4	Inspection of equipment.....	243
7.5	Inspection of production process.....	244
7.6	Inspection of shotcrete placement.....	245
7.7	Inspection of reinforcement assembly.....	247
7.8	Inspection of in-place shotcrete.....	247
7.8.1	General .....	247
7.8.2	Inspection of in-place shotcrete.....	248
7.8.3	Quality inspection of in-placed shotcrete.....	249
7.9	Inspection of structure repaired and strengthened with shotcrete .....	251
<b>Chapter 8 Maintenance.....</b>		<b>252</b>
8.1	Fundamental considerations in maintenance.....	252
<b>Chapter 9 Construction records .....</b>		<b>254</b>
9.1	General .....	254
9.2	Work records .....	254
9.2.1	General .....	254
9.2.2	Inspection records.....	255
9.3	Maintenance records.....	256

## **Part 4 “JSCE Standards for Sprayed Concrete”**

<b>JSCE-D 102-2005 Specification for Set Accelerating Agent for Sprayed Concrete (Mortar) (Draft) .....</b>	<b>257</b>
---	------------

<b>JSCE-F 561-2005 Method of Making Specimens for Compressive Strength Tests of Sprayed Concrete (Mortar) (Draft) .....</b>	<b>268</b>
---	------------



<b>JSCE-F 562-2005 Method of Making Specimens for Durability Tests of Sprayed Concrete (Mortar) (Draft) .....</b>	<b>271</b>
<b>JSCE-F 563-2005 Test Method for Rebound Percentage of Sprayed Concrete (Mortar) (Draft) .....</b>	<b>274</b>
<b>JSCE-F 564-2005 Test Method for Dust Concentration in Air During Spraying Concrete (Mortar) (Draft) .....</b>	<b>279</b>
<b>JSCE-F 565 2005 Test Method for Mechanical Properties, Spraying Performance and Durability of Sprayed Concrete (Mortar) (Draft) .....</b>	<b>284</b>
<b>JSCE-F 566-2005 Method of Making Specimens of Bond Strength Tests of Sprayed Concrete (Mortar) for Repairing and Strengthening (Draft) .....</b>	<b>289</b>
<b>JSCE-G 561-2005 Test Method for Early Strength of Sprayed Concrete (Mortar) by Pull-out Method (Draft) .....</b>	<b>291</b>
<b>JSCE-G 562-2005 Test Method for Early Strength of Sprayed Concrete (Mortar) Using Prism Specimens (Draft) .....</b>	<b>295</b>
<b>JSCE-G 563-2005 Test Method for Strength of Sprayed Concrete (Mortar) for Repairing and Strengthening Using Prism Specimens (Draft) .....</b>	<b>298</b>
<b>JSCE-G 564-2005 Test Method for Length Change of Sprayed Concrete (Mortar) for Repairing and Strengthening (Draft) .....</b>	<b>301</b>