JSCE Guidelines for Concrete No.10

Example of Design Calculations Based on JSCE Standard Specifications for Concrete Structures - Reinforced Concrete Superstructure of Open-Type Wharf-

CONTENTS

1. Intro	1. Introduction		
2. Stru	cture of Open-Type Wharf and Performance Requirements	· 2	
2.1	Specifications of Structure	2	
2.2	Performance Requirements	4	
3. Conditions for Performance Verification			
3.1	Design Service Life	5	
3.2	Materials	- 5	
3.3	Load	5	
3.4	Load Combination and Load Factor	8	
3.5	Flow of Performance Verification	8	
3.6	Limit on Crack Width	10	
3.7	Prerequisite of Verification	10	
3.8	Structure Factor	12	
4. Verification of Floor Slab			
4.1	Structural Overview		
4.2	Performance Verified		
4.3	Load Acting on Floor Slab	14	
4.4	Characteristic Values of Force Resultant	15	
4.5	Design Values of Force Resultant	18	
4.6	Examination of Ultimate Limit State	19	
4.7	Examination of Serviceability Limit State	21	
4.8	Examination of Fatigue Limit State	24	
5. Veri	5. Verification of Beam		
5.1	Structural Overview	29	
5.2	Performance Verified	29	
5.3	Load Acting on Beam	29	

5.5	Design Values of Force Resultant	42
5.6	Examination of Ultimate Limit State	45
5.7	Examination of Serviceability Limit State	47
5.8	Examination of Fatigue Limit State	50
6. Exa	mination at Pile-to-Beam Joint	55
6.1	Introduction	55
6.2	Examination at Pile Head	56
6.3	Anchorage of Reinforcement	58
7. Ver	ification for Durability	59
7.1	Carbonation-Induced Corrosion	59
7.2	Chloride-Induced Corrosion	60
7.3	Freezing and Thawing	62
7.4	Chemical Attack	62
7.5	Alkali-Aggregate Reaction	62
7.6	Water Tightness	63
8. Con	structibility	64
8.1	Construction Planning	64
8.2	Performance of Concrete for Construction	64
8.3	Concrete Production	65
8.4	Ready-Mixed Concrete	65
8.5	Mix Design of Concrete	65
8.6	Verification of Cracking at Construction Stage	67
9. Mai	intenance and Rehabilitation	70
9.1	Maintenance Planning	70
9.2	Maintenance Category A	73
9.3	Maintenance Category B	87
9.4	Estimation of Life-Cycle Cost	90
9.5	Inspection Plan	92
9.6	Evaluation of Inspection Result and Selection of Measure	97
	Record	