

山切1号高架橋



First Yamakiri Viaduct

中日本高速道路(株) 横浜支社 アジア航測(株) 三井住友建設·安部日鋼工業JV 東鉄工業(株) 三井建設·勝村建設JV Central Nippon Expressway Co., Ltd., Yokohama Branch; Asia Air Survey Co., Ltd.; Sumitomo Mitsui Construction Co., Ltd.; Abe Nikko Kogyo Co., Ltd.; Totetsu Kogyo Co., Ltd.; Katsumura Construction Co., Ltd.

概要

山切1号高架橋は、第二東名高速道路と東名 高速道路とを結ぶ清水連絡路の一部をなすPC箱 桁橋である。急峻な山間部で民家やみかん畑に 近接するため、地形改変・周辺環境への影響の 最小化が求められた。そこで、上部工の架設を、 固定支保工による場所打ち架設から、架設桁に よるプレキャストセグメントの架設に替え、地 形改変面積を大幅に削減した。また、張出し架 設工法の適用により、セグメントの製作と架設 速度を均衡させ、橋台部背面の狭小な土工部を セグメントの製作・ストックヤードとして利用 可能にした。

本橋は、架橋地点に十分な作業ヤードが確保 できない場所においてもプレキャストセグメン ト工法の適用が可能であることを示した。

Summary

First Yamakiri Viaduct is a PC box girder bridge on the Shimizu junction connecting the New Tomei Expressway with the present Tomei Expressway. Since the bridge would be located in a steep mountainous area, surrounded by houses and orange fields, the construction of the bridge was required to minimize related geographical changes and its impact on the environment. Accordingly, a precast segment erection method was applied instead of castin-situ box girder erection. In addition, a cantilever erection method balanced segment fabrication and erection speed and made possible the use of narrow space behind the abutment as segment fabrication and stock space.

This project shows that a precast segment erection method is effective for constructions in a narrow space where enough working space cannot be obtained.